

V-TRUSS WALLS & CEILINGS

Specification Sheet

IAPMO UES 2017 US Patent # 6,305,424, B1 7,287,356, B2 • CSI 09 22-36



V-TRUSS Walls & Ceilings is new and improved for superior performance of stucco on overhead surfaces. V-TRUSS Walls & Ceilings is a self-furring welded wire lath for use as an alternative to 3/8" 3.4/yd² rib metal lath specified in ASTM C 847 for use in one and three-coat stucco and as an alternative to the 1.4 lb/yd² woven wire lath specified in ASTM C 1032.

FEATURES

- Designed for overhead and vertical applications
- Wires are class 1 galvanized
- Single mesh lap joints provide for full keying and embedment of the wire
- Sheets are light weight yet strong at 2.2 lb/yd²
- Twin Trac for ease of attachment
- Easy to cut and shape
- Design promotes uniform plaster thickness
- Extra reinforcing at critical crack prone areas
- Attachment points are identified on printed kraft paper
- Minimizes plaster fall out and waste
- Designed for safety and ease of use

DETAILS

- Welded wire sheets 97 1/2" × 28 3/8"
- 0.7" × 1 1/2" rectangular opening
- 44 flattened (CR) line wires spaced approximately 3/4" apart
- 62 cross wires per sheet
- 15 "V" shaped trusses designed to span 24" on center installations. Trusses are furred 3/8" deep by 1.9" C-C
- Stiff backing wires for strong durable sheets
- Twin Tracs for ease of attachment
- Heavy hole-punched kraft paper locked in between primary wires and backing wires
- 5,480 openings in kraft paper
- Lap joints are single mesh at ends and sides
- Perforated tear strip for larger side overlaps, an extra 2" available

PACKAGING

- Palletized 12 sheets per bundle (25 square yards)
- 20 bundles per pallet (500 square yards)
- English/Spanish installation instructions available



All Structa Wire products are designed to reduce waste and can be used in various wall configurations to ensure a high performing, energy-efficient stucco system that meets industry standards. Our products are manufactured from recycled steel and contribute towards LEED points.

With our technically superior products and skilled customer service team, we're able to find solutions to your building requirements, improving the profitability of your projects.

Fully conforms to the requirements for stucco reinforcing as defined in UBC, IBC and IRC building codes.


V-TRUSS WALLS & CEILINGS

Specification Sheet

IAPMO UES 2017 US Patent # 6,305,424, B1 7,287,356, B2 • CSI 09 22-36

Dimensions – Length = 97 1/2" and width = 28 3/8"

Gross Yards – 2.16 per sheet



DETAILS

- A. Welded wire sheets 97 1/2" × 28 3/8"
- B. 0.7" × 1 1/2" rectangular opening
- C. 44 flattened (CR) line wires spaced approximately 3/4" apart
- D. 62 cross wires per sheet
- E. 15 "V" shaped trusses designed to span 24" on center installations. Trusses are furred 3/8" deep by 1.9" C-C
- F. Stiff backing wires for strong durable sheets
- G. Twin Tracs for ease of attachment
- H. Heavy hole-punched kraft paper locked in between primary wires and backing wires
- I. 5,480 openings in kraft paper
- J. Lap joints are single mesh at ends and sides
- K. Tear strip for larger side overlaps, an extra 2" available

Note: Test results are available upon request

Cold Rolled: All longitudinal wires are cold rolled to a structurally designed shape.

Structalath products are for use as alternative laths used as reinforcement for exterior plaster complying with IBC Section 2507, IRC Section R703.6.1 or UBC Section 2508